

PERCOLATION AND DEEPHOLE TEST RESULTS:

LOT #	TEST #	DEEPHOLE DATA	STABILIZED PERCOLATION RATE MIN. / INCH	REQUIRED TRENCH FOOTAGE FOR 3 BEDROOM HOME	MAX. DEPTH OF BOTTOM OF ABSORPTION TRENCH INTO ORIGINAL GRADE
1	1A	SHGW established @ 33" (S)	5 min.	168 { 4-42' LATERALS 2-42' RESERVED	9"
2	14A	SHGW established @ 28" (S)	8 min.	.	4"
3	2	SHGW established @ 25" (S)	5 min.	.	1"
4	13A	SHGW established @ 24" (S)	7 min.	.	0"
6	13	SHGW established @ 27" (S)	7 min.	.	3"
8	8A	SHGW established @ 24" (S)	3 min.	.	0"
9	11	SHGW established @ 31" (S)	6 min.	.	7"
10	8B	SHGW established @ 23" (R)	3 min.	.	0"
11	10	SHGW established @ 36" (R)	5 min.	.	12"
12	9A	SHGW established @ 33" (S)	5 min.	.	9"

(S) = SHALLOW ABSORPTION TRENCHES AT GRADE REQUIRED
 SHGW = SEASONAL HIGH GROUND WATER